



October 20, 2020

**Addendum 1**  
**Bosley Wash Concrete Pad**  
**IFB-20-03056-BW**

This Addendum to the Request for Bids for the above referenced project supersedes all contrary and conflicting information which is hereby supplemented or revised in certain particulars as follows:

Clarifications:

1. Is the #6 x 3' reinforcing steel epoxy coated? **No.**
2. Is Mesa County providing any surveying and testing? **Mesa County will be providing Quality Assurance testing but no surveying. Contractor is required to provide their own Quality Control testing.**
3. What is the elevation do you want the top of concrete pad at? Match existing ground or higher? Do you want concrete pad on a slope from precast concrete box going south to the end of the pad. **The top of the concrete pad is to match the existing concrete pad elevation at the box culvert. Pad does not slope and is to be at the same grade for the length of the pad.**
4. If excavation need built up can existing stockpile material be used? **Existing stockpiled material can be used as fill material to the bottom of the aggregate base if needed.**
5. In the transverse concrete saw cuts, do you want a silicone sealant used? **Sealant is not required in the joints.**

Please note that all Addendums must be acknowledged with each bid package.

All remaining requirements of the Invitation for Bids remain unchanged.

Laura J. Page, P.E.  
Mesa County Public Works-Engineering Department  
Construction Group Manager